

ADDENDUM #3

TO

CITY OF SOUTH PORTLAND, MAINE

THORNTON HEIGHTS SEWER SEPARATION

PHASE 3

(BID# 22-16)

February 5, 2016

Prepared By:

Sebago Technics, Inc.
75 John Roberts Road, Suite 1A
South Portland, Maine 04106-6963

Phone: 207-200-2100

Fax: 207-856-2206

ADDENDUM NO. 3

THORNTON HEIGHTS SEWER SEPARATION PHASE 3

BID #22-16

The Contract Documents govern all aspects of the project. Informal discussions held during the Pre-Bid Conference, by telephone or email are informational only. All official changes to the Contract Documents are made only by addenda. The following changes and additional information are hereby made a part of the Contract Documents.

BIDDER QUESTIONS: Notice is hereby given that Addendum #3 provides clarification for questions asked by Bidders after the Pre-Bid meeting held on January 19, 2016 and prior to the Bid Opening Date of February 9, 2016.

1. Question: I would like to try to get some clarification on the chain link fence specifications. One of the notes on sheet 83 calls for top and bottom braces. It is normal to have a top rail, but we are not sure if they intend to also have a bottom rail. One of the notes calls for a brace rail at each corner section, but the drawing shows a middle rail. Do they want a continuous middle rail on the fence?

Answer: A continuous top rail is required. A bottom rail is not required, the bottom of the fence shall include a tension wire. A brace rail is only required at corners and at sections adjacent to the gates. A continuous middle rail is not required.